

Price Schedule

Name of work : P&F of ACP Sheet Shed at NICPD, Gurgaon

Sr. No.	Description of Item	Qty.	Unit	Rate	Amount
1.	Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc. to with stand stresses without sagging.	120	Sq. mt.		
2.	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position at a height of 10.5 feet including grouting the and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. • Hot finished welded type tubes.	1100	Kg.		
3.	Providing and Laying CC in 1:1.5:3 ratio (1 cement: 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size) cement concrete including providing form work etc. complete.	0.08	cum		
4.	Providing and Fixing Stainless Steel 304 grade Expandable fasteners through drilling holes in the beams including tightening with SS and neoprene washers. 150 mm fasteners with 12 mm dia	12	each		

Grand Total :

Accepted by me

Name

Address

Mob. No.